


Executant 2019 C1 contract

Investitie C1 contract

Obiect LB . straine + sc. B

Deviz 6 INSTALAT instalatia de incalzire



APROB  
COMANDANTUL U.M. 02192

Octavian TARABUTO

antemasuratoare

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat	Sp.man	Sp.uti
Corectii						
Denumire resursa						
Observatii						
Liste anexa						
1	RPIF01A1	82 MP	1,536.00000			
GOLIRE INSTALATIE DE INCALZIRE CENTRALA *						
320corpX20elemX0,24mp						
2	RPSA17C1	82 M	323.00000			
INLC.TV.PVC.TIP G IN COL.LA LOC.SOC.CULT.PE PORT.						
PINA LA 10 M D= 40 MM						
63m*2*2+16*2*2+3.5*2 =2/3demisol lb engl perimetru						
3	6716504	M	333.00000			
TEAVA POLIPROPILENA CU FOLIE AL.(PP-AL) DN=40MM						
4	RPSA17B1	82 M	528.00000			
INLC.TV.PVC.TIP G IN COL.LA LOC.SOC.CULT.PE PORT.						
PINA LA 10 M D= 32 MM						
8m*660ml parter+et.l						
5	6716503	M	544.00000			
TEAVA POLIPROPILENA CU FOLIE AL.(PP-AL) DN=32MM						
66col parter si etaj I						
6	RPSA17A1	82 M	528.00000			
INLC.TV.PVC.TIP G IN COL.LA LOC.SOC.CULT.PE PORT.						
PINA LA 10 M D= 25 MM						
etaj II si III 66 col*8ml						
7	6716502	M	544.00000			
TEAVA POLIPROPILENA CU FOLIE AL.(PP-AL) DN=25MM						
8	RPSA16C1	82 M	2,520.00000			
INLC.TV PVC.TIP G.IN LEG.LA OB.SANT.MONT.AP.LA LOC						
SOC.CULT.PE PORT.PINA LA 6 M D= 20 MM						
9	8813487	BUCATA	2,595.00000			
TEAVA PPR/AL PN20 SDR6 L=4M D=20X3,4MM (M 429455)						

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat
Corectii	Denumire resursa	Observatii	Liste anexa	Sp.man Sp.uti
10	RPSA17D1	82 M	696.00000	-100%
INLC.TV.PVC.TIP G IN COL.LA LOC.SOC.CULT.PE PORT. PINA LA 10 M D= 50 MM subsol engleza+demisol depozit in 2 tr. perimstru				
11	6716505	M	716.00000	
TEAVA POLIPROPILENA CU FOLIE AL.(PP-AL) DN=50MM ubsol engl 448+depozit 248 perim)*1.03				
12	RPIC79A1	82 BUCATA	4,491.00000	-100%
INLOCUIT SAU INTERCALAT FITINGURI (RACORD OLANDEZ, DOP RADIATOR,MUFA REGLAJ) 3/8-1 "				
L:11315 -0003:4117930 -COT FONTA MALEABILA A1 S474 DN 20 3/4				
13	6719485	BUCATA	1,764.00000	
COT DIN POLIPROPILENA, AVIND DIAMETRUL 20 MM				
14	6719486	BUCATA	358.00000	
COT DIN POLIPROPILENA, AVIND DIAMETRUL 25 MM				
15	6719549	BUCATA	140.00000	
RACORD DREPT DIN POLIPROPILENA, DIAMETRUL 40 MM 1 1/4"				
16	6719525	BUCATA	8.00000	
REDUCTIE DIN POLIPROPILENA,AVIND DIAMETRUL 50 * 40 MM				
17	6719518	BUCATA	140.00000	
REDUCTIE DIN POLIPROPILENA,AVIND DIAMETRUL 32 * 25 MM				
18	6719521	BUCATA	42.00000	
REDUCTIE DIN POLIPROPILENA,AVIND DIAMETRUL 40 * 32 MM				
19	6721124	BUCATA	157.00000	
CRUCE PP20				

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat
Corectii				Sp.man
Denumire resursa				Sp.uti
Observatii				
Liste anexa				
20	6719494	BUCATA	320.00000	
	TEU DIN POLIPROPILENA, AVIND DIAMETRUL 25 MM			
21	6719496	BUCATA	150.00000	
	TEU DIN POLIPROPILENA, AVIND DIAMETRUL 40 MM			
22	6719957	BUCATA	120.00000	
	RACORD DREPT DIN POLIETILENA, FILET EXTERIOR, D=20 -3/4"			
23	6719515	BUCATA	320.00000	
	REDUCTIE DIN POLIPROPILENA, AVIND DIAMETRUL 25 * 20 MM			
24	6719477	BUCATA	290.00000	
	MUFA DIN POLIPROPILENA AVIND DIAMETRUL EXTERIOR 20 MM			
25	6719478	BUCATA	292.00000	
	MUFA DIN POLIPROPILENA AVIND DIAMETRUL EXTERIOR 25 MM			
26	6719480	BUCATA	92.00000	
	MUFA DIN POLIPROPILENA AVIND DIAMETRUL EXTERIOR 40 MM			
27	6719481	BUCATA	292.00000	
	MUFA DIN POLIPROPILENA AVIND DIAMETRUL EXTERIOR 50 MM			
28	SA43C1	82 BUCATA	120.00000	
	BRATARA PT.FIXAREA COND.OTEL+PVC DE ALIM.CU APA+GA ZE, MONT.PRIN INCASTRARE, COND.AVIND D= 1/2 TOLI			
29	SA43D1	82 BUCATA	120.00000	
	BRATARA PT.FIXAREA COND.OTELPVC DE AL&MCCU APAFGA ZE, MONT.PRIN INCASTRARE, COND.AVIND D= 3/4 TOLI			

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat
Corectii				Sp.man
Denumire resursa				Sp.uti
Observatii				
Liste anexa				
30	SA43E1	82 BUCATA	64.00000	
BRATARA PT.FIXAREA COND.OTEL+PVC DE ALIM.CU APA+GA ZE,MONT.PRIN INCASTRARE,COND.AVIND D=1 TOLI				
31	SA43F1	82 BUCATA	34.00000	
BRATARA PT.FIXAREA COND.OTEL+PVC DE ALIM.CU APA+GA ZE,MONT.PRIN INCASTRARE,COND.AVIND D=1 1/4 TOLI				
32	SA43G1	82 BUCATA	36.00000	
BRATARA PT.FIXAREA COND.OTEL+PVC DE ALIM.CU APA+GA ZE,MONT.PRIN INCASTRARE,COND.AVIND D=1 1/2 TOLI				
33	RPCU12B1	82 BUCATA	264.00000	
STRAPUNGERI IN PLANSEE DE BETON ARMAT CU GROSIMEA 10-11CM SI SECTIUNE SUB 150CMP				
34	RPID03A2	82 BUCATA	640.00000	
INLOCUIT ROBINET CU VENTIL CU DUBLU REGLAJ COLTAR SAU DREPT CU DIAM.1/2"				
35	RPID33A1	82 BUCATA	70.00000	
MONTARE ROBINET DE TRECERE PE COND.AERISIRE 3/8' *				
36	4501090	BUCATA	70.00000	
ROBINET DE AERISIRE				
37	IC37A1	82 KG	500.00000	
SUPPORTI CONDUCTE,TUBURI DIVERSE,COLECTOARE-DISTRIB APARATE RECIPIENTI DIV.PINA LA 2KG.INCL./BUC				
38	5709410	BUCATA	1,088.00000	
CONSOLA PTR.RADIATOR CU LUNGIMEA DE 250 MM				
39	RPID12C1	82 BUCATA	70.00000	
INLOCUIT ROBINET CU VENTIL DIN FONTA CU FLANSE DE 50 MM				

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat
Corectii	Denumire resursa	Observatii	Liste anexa	Sp.man Sp.uti
40	RPIB01A1	82 MP	1,536.00000	
DEMONTARE RADIATOR DE PE POZITIE*				
320 corpuri x 20 elem x0,24mp				
41	IB02P01	82 BUCATA	320.00000	
MONTARE CONVECTORRADIATOR TIP PANOU 2 RIND TEVI,RAC				
ORDAT CU MUFA H=624MM AVIND >15 TEVI VERTICALE				
L:11312 -0051:5701386 -CONVECTORRADIATOR C.R.P. 1 RIND 624/ 4 MUFA NII 341				
42	RPIC79A1	82 BUCATA	1,189.00000	
INLOCUIT SAU INTERCALAT FITINGURI (RACORD OLANDEZ,				
DOP RADIATOR,MUFA REGLAJ) 3/8-1 "				
43	6719477	BUCATA	1,189.00000	
MUFA DIN POLIPROPILENA AVIND DIAMETRUL EXTERIOR 20				
MM				
44	TRB05B24	82 TONE	4.00000	
TRANSPORTUL MATERIALELOR PRIN PURTAT DIRECT,MATERI				
ALE INCOMODE PESTE 25 KG DISTANTA 40M \$				
45	TRA02A10	82 TONE	4.00000	
TRANSPORTUL RUTIER AL MATERIALELOR,SEMIFABRICATELO				
R CU AUTOCAMIONUL PE DIST.= 10 KM. \$				

Intocmit

p.c.c. Ing.

Lenuta IONITA

*Ionita*

Verificat

comandor

Doru COSOFRET

*[Signature]*

