

Executant 2019 C1 contract
 Investitie C! contract
 Obiect LB . straine + sc. B
 Deviz 9 retea alim apa pavilion



antemasuratoare teava alim. Cu apa din camine cu trecere

prin tot subsolul pavilionului

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat	Sp.man	Sp.uti
	Corectii					
	Denumire resursa					
	Observatii					
	Liste anexa					
1	TSA03A1	82 M CUB	20.00000			
	SAPAT.MAN.IN SPATII LIMIT.SUB 1M LATIME,FARA SPRIJ CU TALUZ INCL.TER.SLAB COEZIV<0.75M ADINC.,T.USOR 25mlx0.8 din camin pana la intrare pavilion					
2	RPCT09H1	82 M CUB	2.00000			
	SPARGEREA PARTIALA CU MIJLOACE MEC SI MANUALA A EL EMENTELOR DE CONS.DIN BET.ARM.SI SIMPLU EXEC.FIN * 2 camine pav se alim in cele 2 capete					
3	CA01A1	82 M CUB	2.00000			
	TURNARE BETON SIMPLU IN FUNDATII(CONTINUE,IZOLATE) SI SOCLURI CU VOLUM <3MC					
	L:10173 -0019:CZ0104A1 -PREPARARE BETON B100 CU BALAST,GRANULATIA<31MM CU CIMENT F25,IN INSTALATII CENTRALIZATE \$					
4	ACE08A1	82 M CUB	3.88000			
	UMPLUTURA IN SANT.LA COND.DE ALIM.CU APA SI CANALI ZARE CU: NISIP \$					
5	ACE08C1	82 M CUB	1.00000			
	UMPLUTURA IN SANT.LA COND.DE ALIM.CU APA SI CANALI ZARE CU: PIATRA SPARTA IN JURUL TUB.DE DRENAJ \$					
6	ACA15C1	82 M	123.00000			-100%
	MONTARE TUBURI DE PRES.DIN POLIEST.ARMATE CU FIBRE STICLA PRIN INFAS.,IN PAM.EXT.CLAD.,MF+CEP P,D100 teava alim. cu apa din camine +travers subsol pav.					
7	9126002	M	123.00000			
	TEAVA NG PVC TIP UDN=110					
8	6110510	KG	9.00000			
	ADEZIV PTR LIPIT P.V.C.					
9	ACA13A1	82 BUCATA	20.00000			-100%
	IMBINARE CU MUFA CU FLANSA CS39-77 A TEVILOR PVC M MUFATE CU D=125X6 \$					

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat	Sp.man	Sp.uti
10	9125003	BUCATI	8.00000			
	COT PVC TIP U DN110					
11	9125021	BUCATI	12.00000			
	MUFA PVC TIP U DN110					
12	ACA13A1	82 BUCATA	13.00000			-100%
	IMBINARE CU MUFA CU FLANSA CS39-77 A TEVILOR PVC M MUFATE CU D=125X6 §					
13	9125002	BUCATI	9.00000			
	TEU REDUS PVC DN 110-50					
14	9125001	BUCATI	3.00000			
	TEU E AL PVC DN110					
15	9125030	BUCATI	1.00000			
	REDUCTIE PVC TIP „D” DN=210-110					
16	89	BUCATA	9.00000			
	GARNITURI NEOPREN					
17	IC18XF	91 BUCATA	3.00000			-100%
	FLANSA ROTUNDA PLATA PT.SUDARE,MONT.LA COND.DIN TE AVA NEAG OL PT.INST.CU PN6,10SAU16ATM D=200-250 MM					
18	78	BUCATA	3.00000			
	FLANSA RACORD DN110					
19	RPSA37I	99 BUCATA	13.00000			-100%
	MONTAREA UNUI COMPENSATOR DE DILATATIE, FORMAT U S AU LIRA, DIN TEAVA DIN PVC TIP GREU (G), D= 110MM					

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat
Corectii				Sp.man
Denumire resursa				Sp.uti
Observatii				
Liste anexa				
20	9	BUCATA	9.00000	
RACORD HIBRID CONECTARE TEAVA PEID PVC DN110				
21	9125009	BUCATA	4.00000	
SA BRANSARE PVC TIP U DN 110-1/2"				
22	RPIC27N1	82 M	123.00000	
DEMONTARE TEVI CONSTR LEG APARAT 114X4 MM*				
23	RPID12C1	82 BUCATA	4.00000	
INLOCUIT ROBINET CU VENTIL DIN FONTA CU FLANSE DE 50 MM				
24	RPID10D1	82 BUCATA	2.00000	
DEMONTARE ROBINET VENTIL FONTA 100,125 MM*				
25	RPID06E2	82 BUCATA	2.00000	
INLOCUIT ROBINET CU SERTAR PANA DIN FONTA CU FLANS E SI CORP OVAL CU DIAM. DE 100 MM				
26	RPID12F1	82 BUCATA	2.00000	
INLOCUIT ROBINET CU VENTIL DIN FONTA CU FLANSE DE 100MM				
27	RPID12H1	82 BUCATA	4.00000	
INLOCUIT ROBINET CU VENTIL DIN FONTA CU FLANSE DE 150MM				
28	RPAB01F1	82 BUCATA	2.00000	
RIDICARE LA NIVEL A CAPACELOR (I=20CM) CAMINELOR D E VIZITARE PESTE 100KG PE PLACA PREF.BET ARMAT *				
29	IZH07B1	82 MP	34.00000	
IZOL.COND.CU SALTELE VATA MIN.I-SPS1 GATA CONF.GRO S.30-60MM.CU CIRC.PESTE TERMOIZ.PESTE 35 CM.				
L:11245 -0001:2606743 -SALTEA VATA MINERALA SPS2 3000X 600X 50 S5838/3				

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat
Corectii				Sp.man
Denumire resursa				Sp.uti
Observatii				
Liste anexa				
30	SA44G1	82 BUCATA	36.00000	
BRATARA PT:FIXAREA COND.OTEL+PVC DE ALIM.CU APA+GA ZE,MONT.PRIN IMPUSCARE,COND.AVIND D=1 1/2 TOLI				
31	SA44J1	82 BUCATA	246.00000	
BRATARA PT:FIXAREA COND.OTEL+PVC DE ALIM.CU APA+GA ZE,MONT.PRIN IMPUSCARE,COND.AVIND D=3 TOLI				
32	TRB05A25	82 TONE	14.90000	
TRANSPORTUL MATERIALELOR PRIN PURTAT DIRECT.MATERI ALE INCOMODE SUB 25 KG DISTANTA 50M \$				
33	TRA01A10	82 TONE	14.90000	
TRANSPORTUL RUTIER AL MATERIALELOR,SEMIFABRICATELO R CU AUTOBASCULANTA PE DIST.= 10 KM. \$				

Intocmit
p.c.c. Ing.
Lenuta IONITA

Yeuite.

Verificat
comandor
Doru COSOFRET


