


Executant 04 pav i
Investitie 041 pav i
Obiect 2 infirm. 2025
Deviz 3 electrice



antemasuratoare

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat	Sp.man	Sp.uti	Pret materiale	Val. materiale
Corectii							Pret manopera	Val. manopera
Denumire resursa							Pret utilaj	Val. utilaj
Observatii							Pret transport	Val. transport
Liste anexa							Nr.ore/UM	TOTAL A
							Greutate/UM	Greutate totala

1 RPEE01D1 82 BUCATA 10,00000

INLOC INTRERUPATOR MANUAL UNIPOLAR CONSTRUCTIE NOR
MALA APAR DIBL LEMN CUMPANA BACHELITA

A-N2835/18.06.2025/02022



L:12010 -0001:5519173 -INTRERUPTOR PACHET BIPOLAR SIMBOL 0520 25A ROTATIV

2 ED12B1 82 BUCATA 4,00000

APARAT DE SEMNALIZARE OPTICA (INDICATOR POZITIE,CA
SETA,LAMPA SEMNALIZ.)

L:12025 -0016:5537955 -CUTIE SEMNALIZARE OPTICA COD 4370

3 RPEE02F1 82 BUCATA 42,00000

INLOC COMUTATOR SERIE UNIP APARENT CONSTR NORMALA
DIBLURI LEMN CUMPANA BACHELITA

L:12011 -0006:5520378 -COMUTATOR CRUCE CUMPANA PT.SIMBOL 024 10A 250V S 3185

4 RPEG02C1 82 BUCATA 4,00000 -100%

INLOC TABL ELECT PE STELAJ MET MODULAT CU MASCA PE
RTINAX PE PERETE SAU NISE SUPR < 0,91-1,50MP

5 8807126 BUCATA 4,00000

TABLOU ELECTRIC ARIANNE2

6 EC14F1 82 BUCATA 1,00000

CUTIE TERMIN.PT.INST COMANDA SEMNAL BLOCARI INCL.L
EGATURA LA CLEME TABLOU SAU APARAT 49-61 CONDUCTE*

7 W1SC01A 99 BUCATA 1,00000

PANOU,STELAJ,DULAP METALIC (PROTECTIE,COMANDA,MASU
RA,SEMNALIZARE,SERVICII PROPRII,ETC) ECHIPAT

8 W1MD04A 99 BUCATA 10,00000

SIR DE CLEME CONECTOR ELECTRIC DE 10-63A

L:W1ML003-0006:5537499 -CLEMA DE LEG 95MMMP, 315A

9 W1MD05A 99 BUCATA 10,00000

LEGAREA CONDUCTORULUI LA CIRCUITELE SECUNDARE INTR
E CUTIA TERMINALA SI SIRUL DE CLEME

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat Sp.man Sp.uti	Pret materiale Pret manopera Pret utilaj Pret transport Nr.ore/UM Greutate/UM	Val. materiale Val. manopera Val. utilaj Val. transport TOTAL A Greutate totala
Corectii	Denumire resursa	Observatii	Liste anexa			
10	W1ME02B	99 BUCATA	4,00000			
	TRECERE IZOLATA INTERIOR-EXTERIOR PRIN PERETE, 20 KV					
	L:W1M006B-0006:5600662 -IZOLATOR SUPT ARMARE INT.II 12,50 125 20KV S 5852/2					
	L:W1M007G-0012:5211526 -CAPAC CI-3,75-125					
	L:W1M007I-0012:5211526 -CAPAC CI-3,75-125					
	L:W1M007J-0006:5211520 -ARMATURA INFERIOARA AS-12,5-125					
	L:W1ML008-0011:5201012 -BARA DE TRECERE BTB 20 CU, 1020A 2X30X5MM					
11	W1MN03A	99 KG	300,00000			
	CONDUCTOR PT. LEGAREA LA PAMINT A APARATELOR MONTATE IN EXTERIOR					
	L:W1M078B-0002:4831965 -CONDUCTOR OTEL ZINCAT 150 MMP					
12	W1MO40A	99 BUCATA	4,00000			
	MANSON DE LEGATURA DIN SET MAT.PREFAB. PT. CABLU MONOFAZ. 20 KV IZOL. POLIET., SECT. 1X95 MMP					
	L:W1ML099-0011:5208967 -MANSON TERMOCONTRACTIBIL SXSU 5131					
13	W1MO42A	99 BUCATA	6,00000			
	MANSON DE LEGATURA MIXT INTRE CABLU TRIFAZ. IZOL. HIU 3X95 MMP SI CABLU MONOFAZ. IZOL. MP 95 MMP					
	L:W1ML101-0020:5208999 -MANSON TERMOCONTRACTIBIL EPKU-24D/1XU-3XU					
14	RPED16A	99 M	286,00000			
	MONT.CABL.EL.SEMICOND.CU NUL DIN CUPRU,ARMAT.SIRMA OL ZN.PT.TENS.3,5-6KV,ACMYHCSAIV, S=3X25+16MMP					
	L:EL03D -0038:7319369 -DOZE RAMIFICATIE BACHELITA PT.CABLU IPE 4 IESIRI					
	L:EL15E -0103:4815142 -CABLU CSYEY MASIV 12 X 4 S 8779					
15	RPEF11A05	82 BUCATA	40,00000			
	INLOC CORP ILUM PT LAMPI FLUORESCENTE TUBULARE TIP CGA 240 2X40W DIBLURI LEMN FARA REFLECTOR					
	L:12009 -0010:5102528 -CORP ILUMINAT FLUORESCENT CGA 2X40 W					
16	RPEF03P1	82 BUCATA	98,00000			
	INLOCUIRE APLICA CU 4 BRATE DIBLURI DE PLASTIC					
	L:12009 -0071:5106043 -LAMP MONOBLOC ILUM.SALI PUBL. CU RELEU STICLA COS P					
17	RPEE03A3	82 BUCATA	42,00000			
	INLOC PRIZA BIPOL INGROPAT CONSTR NORMALA BACHELIT A DREPTUNGHULARA					
18	RPEE03A4	82 BUCATA	336,00000	-100%		

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat Sp.man Sp.uti	Pret materiale Pret manopera Pret utilaj Pret transport Nr.ore/UM Greutate/UM	Val. materiale Val. manopera Val. utilaj Val. transport TOTAL A Greutate totala
Corectii						
Denumire resursa						
Observatii						
Liste anexa						
INLOC PRIZA BIPOL INGROPAT CONSTR NORMALA AMINOPLA ST DUBLA						
19	7313039	BUCATI	312,00000			
CUTIE CU 4 PRIZE MONTATE ST						
20	7313041	BUCATI	24,00000			
CUTIE 3 PRIZE MONTATA ST						
21	RPED01C1	82 M	2.320,00000			
INLOC CABLU ENERG INST APARENT CU SCOABE PE CONS FIXATE IN PERETE CABLU SECT < 4MMP						
L:12007 -0022:4802688 -CABLU ENERGIE CYABY 0,6/ 1KV 3X 16 M S 8778						
22	RPEB02A9	82 M	4.324,00000			
INLOCUIRE COND DE CU FY IZOL SECT 4MMP INTROD IN T UB PVC,PEL,TEAVA						
23	RPEB02A7	82 M	4.216,00000			
INLOCUIRE COND DE CU FY IZOL SECT 1,5MMP INTROD IN TUB PVC,PEL,TEAVA						
24	RPEB02A8	82 M	6.346,00000			
INLOCUIRE COND DE CU FY IZOL SECT 2,5MMP INTROD IN TUB PVC,PEL,TEAVA						
25	RPEA10E1	82 M	260,00000			
INLOC TEAVA PVC TIP U DIAM EXT 50MM < 10M LUNG INS TALAT APARENT PE DIBLURI DE LEMN						
26	EC04XD	91 M	860,00000	-100%		
CABLU PT.ENERG.ELECT.SAU SEMNALIZ.TRAS PRIN TUB SA U TEAVA PROTECTIE,CABLU CU MASA 4,01-6,00 KG/M						
27	6312786	KG	260,00000			
JGHEABURI PT.CABLURI, ZINCATE						
260 ml						
28	3270072	M	600,00000			
PAT CABLU 20X15						

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat	Pret materiale	Val. materiale
Corectii				Sp.man	Pret manopera	Val. manopera
Denumire resursa				Sp.uti	Pret utilaj	Val. utilaj
Observatii					Pret transport	Val. transport
Liste anexa					Nr.ore/UM	TOTAL A
					Greutate/UM	Greutate totala

29 RPEA01D1 82 M 7.215,00000

INLOCUIRE TUB IZOLANT IP-PVC IN ZIDARIE TENC DIAME
TRUL EXT 25 MM IN CANTITATI < 3M LUNGIME

30 RPCU17A5 82 M 3.107,00000

ASTUPAREA SANTURILOR IN ZIDARIE CU MORTAR DE IPSOS
-VAR SI NISIP SANTUL AVIND SECT.DE 20-30 CMP

31 RPEH08B1 82 M 180,00000

INLOC CONDUCT DE COBORIRE SAU LEGARE LA CENTURA AP
AR PE ZID BANDA OL DE 25X4 MM

32 EG08B1 82 M 180,00000

COND.LEG.PAM.INST.PARATRASNET PROT.LEG.PAMINT MONT
.PAM.BANDA OL ZINC.40X4MM MONT.IN TEREN TARE *

33 W1R06A1 82 M 16,00000

ELECTROD DIN TEAVA DE OTEL DE DOI TOLI SI JUMATATE
PENTRU LEGAREA LA PAMINT IN TEREN NORMAL

34 TSA04C2 82 M CUB 16,00000

SAP.MAN.IN SPATII LIMIT.SUB 1M CU SPRIJ.SI EVAC.MA
N.IN PAM.IMBIB.CU APA ADINC.0,0-1,5M,T.TARE

35 TSD01C1 82 M CUB 16,00000

IMPRASTIEREA CU LOPATA A PAMINT.AFINAT,STRAT UNIFO
RM 10-30CM.GROS CU SFARIM.BULG.TEREN TARE

36 TSD04C1 82 M CUB 16,00000

COMPACTAREA CU MAI.DE MINA A UMPLUT.EXECUT.PE STRA
T.CU UDAREA FIEC.STRAT DE 20CM GROS.T.NECOZIV

37 EG10A1 82 BUCATA 1,00000

CUTIE CU ECLISA DE LEGATURA PT.CENTURA DE INPAMINT
ARE

38 W1R06XC 93 BUCATA 6,00000

MONTARE TIJA METALICA PENTRU PARATRASNET,MONTATA P
E SUPTOR DE BETON,LA INALTIME DE 10M

39 CE24D 93 BUCATA 10,00000

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat	Pret materiale	Val. materiale
Corectii				Sp.man	Pret manopera	Val. manopera
Denumire resursa				Sp.uti	Pret utilaj	Val. utilaj
Observatii					Pret transport	Val. transport
Liste anexa					Nr.ore/UM	TOTAL A
					Greutate/UM	Greutate totala

DIV.ACESORII LA INVELIT.ROZETA MANSON TB.ZN. 0,5MM
LA INTR.MONT.IN PARAP.PICIOARE ANTENE,PARATRAZNETE

40 TCA28A1 82 BUCATA 6,00000

ELEMENTE DE PROTEJARE A INST. TC : PARATRASNET CU
ECLATOARE

41 RPEI03B 99 M 80,00000

INLOC.CIRC.PNEUM.AMCR,TV.CUPRU,AL,PVC CU D=12MM,IN
CL.PIESE DE RACORD.,PROB.SI PUNEREA IN FUNCT.

L:EL03G -0038:7319369 -DOZE RAMIFICATIE BACHELITA PT.CABLU IPE 4 IESIRI
L:EL15F -0174:4817358 -CABLU CU IZOL MANT CAUC MCCGI 3 X 95+50 S 12220/6

42 RPEG20A1 82 BUCATA 4,00000

DEMONTARE TABLOU DISTRIB METALIC*

43 RPEG02C1 82 BUCATA 2,00000 -100%

INLOC TABL ELECT PE STELAJ MET MODULAT CU MASCA PE
RTINAX PE PERETE SAU NISE SUPR < 0,91-1,50MP

L:12061 -0007:7348918 -TABLOU DISTRIBUTIE TIP INCHIS CU BARE AL 350 A

44 7322263 BUCATA 2,00000

FIRIDA PRINCIP.BRANSAMENT VAR.E2 NR.DES.407/76 PLA
NSA 2

45 ED08S1 82 BUCATA 8,00000

PRIZA TRIFAZICA,DE 63A,CAPSULATA IN SILUMINIU,EXCL
USIV CONSOLA SI RACORDAREA

L:12017 -0015:5535933 -PRIZA SI FISA TRIPOL.BACHEL.CUCONTACT PROTEC.380V,25A

46 EF02A1 82 BUCATA 8,00000

TABLOU ELECTRIC PE SCHELET MET.CU MASCA MONT.PERET
E SAU IN NISA,TABLOUL CU SUPR.<0,30MP

L:12061 -0026:5500744 -CUTIE ETANSA INTRERUP. III 16A 380V SIMBOL 7030.

47 RPEG14D1 82 BUCATA 8,00000

COMPLETARE TABLOU PE PLACA MARMORA CU UN CIRCUIT S
IGURANTA LS TRIFAZIC 25 A *

L:12001 -0076:5524805 -COMUTAT.CU CAME C-16 500VCA CU 2 ET.COD 9821
L:12015 -0002:5537230 -SOCLU PT.SIGURANTA CU LEGATURIIN FATA LF60A SIMB.2040

48 RPEG14A1 82 BUCATA 8,00000

COMPLETARE TABLOU PE PLACA MARMORA CU UN CIRCUIT S

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat	Pret materiale	Val. materiale
Corectii				Sp.man	Pret manopera	Val. manopera
Denumire resursa				Sp.uti	Pret utilaj	Val. utilaj
Observatii					Pret transport	Val. transport
Liste anexa					Nr.ore/UM	TOTAL A
					Greutate/UM	Greutate totala
IGURANTA LS MONOFAZIC 25 A *						
L:12001 -0057:4826907 -CONDUCTOR FY 1X 4 S 6865						
L:12015 -0001:5537228 -SOCLU PT.SIGURANTA CU LEGATURIIN FATA LF25A SIMB.2030						
49	EF05D1	82 BUCATA	8,00000			
TABLOU DE APARTAMENT CU 4 CIRCUITE TIP BLOC ELECTR IC. tabechipat cu diferent 30mA,sig. bip 25A,32A						
50	EF03C1	82 BUCATA	1,00000			
TABLOU ELECTRIC PANOUL,DULAP,CELULA SAU PUPITRU GAT A ECHIPAT,CU GREUTATEA 301-500KG						
L:12061 -0007:7348918 -TABLOU DISTRIBUTIE TIP INCHIS CU BARE AL 350 A						
51	RPED05E1	82 M	280,00000			
INLOC CABLU ENERG TRAS IN TUB METALIC PT RACORD LA MOTOARE TABL APAR EXCLUS TUB PROT CABL SECT 35MMMP cablu alimentare CYABY 5x35						
L:12007 -0030:4803113 -CABLU ENERGIE CYABY 0,6/ 1KV 4X 35 M S 8778						
52	VC01C1	82 BUCATA	2,00000			
MONTAREA VENTILATORULUI AXIAL GR.TOTALA 50-200KG						
53	8809145	BUCATA	2,00000			
VENTILATOR IN LINIE TURBO 150 - 500MC/H						
54	RPSE27A	99 BUCATA	5,00000			
MONTAREA USCATORULUI DE MIINI SAU DISTRIBUTORULUI AUTOMAT DE SAPUN LICHID,PE PERETE DIN ZIDARIE						
L:SL44D -0044:7356849 -USCATOR DE MAINI						
L:SL44I -0011:6719251 -DIBLU PVC MARIMEA 1 NII-1030-75						
55	RPSC12A1	82 BUCATA	5,00000			
INLOC.COMPL.CAZ.BAIE TABLA EMAIL DE 95 L. MONTAT P E SOBA DE FONTA						
56	8807657	BUCATA	5,00000			
GRUP TERMIC BITHERM 35/80 -37.2KW/BOILER 80LT						
57	TRA01A10P	82 TONE	35,50000			
TRANSPORTUL RUTIER AL PAMINTULUI SAU MOLOZULUI CU AUTOBASCULANTA DIST.=10 KM \$						

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat	Pret materiale	Val. materiale
Corectii				Sp.man	Pret manopera	Val. manopera
Denumire resursa				Sp.uti	Pret utilaj	Val. utilaj
Observatii					Pret transport	Val. transport
Liste anexa					Nr.ore/UM	TOTAL A
					Greutate/UM	Greutate totala

58 TRA02A15 82 TONE 35,50000

TRANSPORTUL RUTIER AL MATERIALELOR, SEMIFABRICATELO
R CU AUTOCAMIONUL PE DIST.= 15 KM. \$

Greutate totala
Total ore

Total materiale
Total manopera
Total utilaj
Total transport
Total A

Indoniz
loc *Yout*
Lenutz *JOKITA*

Verificat
DIRECTOR GENERAL ADMINISTRATIV
Celor
Radu BOBDEL



